Environmental Protection Agency

Horiba Emission Analysis System CO₂ Interference Procedure

This procedure is written for the Environmental Protection Agency, National Vehicle and Fuel Emissions Laboratory (NVFEL) internal use. The use of specific brand names by NVFEL in this procedure are for reference only and are not an endorsement of those products. This document may be used for guidance by other laboratories.

NVFEL Reference Number

305

Implementation Approval

Original Procedure Authorized by EPCN #245 on 11-8-99

Revision Description

Table of Contents

1.	Purpose
2.	Test Article Description
3.	References
4.	Required Equipment
5.	Precautions
6.	Visual Inspection
7.	Test Article Preparation
8.	Test Procedure
9.	Data Input
10.	Data Analysis
11.	Data Output
12.	Acceptance Criteria
13.	Quality Provisions
	<u>Figures</u>
Figure 1	Water Bubbler6
Figure 2	On-Screen Keyboard
Figure 3	"Utility" screen
Figure 4	Check/Test Button
Figure 5	Interference Screen 9
Figure 6	C02 Configuration Button
Figure 7	C02 Interference Check Config Screen

Figures Continued

Figure 8	Reset Correction Factor screen	11
Figure 9	Interference Check Results Reset Screen	11
Figure 10	Z/S Calibration Screen	12
Figure 11	Select Range Screen	12
Figure 12	Select External Gas Screen	13
Figure 13	Enter C02 Concentration Screen	13
Figure 14	Enter T1 Screen	14
Figure 15	Start/Stop Screen	14
Figure 16	Analyzer Calibration Screen	15
Figure 17	Status Indicators Screen	15
Figure 18	Verify Results Screen	16
Figure 19	Result Display Button	16
Figure 20	Interference Check Results subpanel	17
Figure 21	Hardcopy subpanel	17
Figure 22	Print Subpanel	18
Figure 23	"Utility" Screen	18
Figure 24	Analyzer Calibration Screen	19
Figure 25	Select User Level Screen	19
Figure 26	Select "Normal" User Screen	20

1. Purpose

The purpose of this procedure is to describe the equipment and procedure required to perform a CO₂ Interference Check on the Horiba, Mexa-7000, Automotive Emission Analysis System. The practice shall be performed at six month intervals.

The following additional equipment is required:

Portable CO₂ interference kit with flex line

Container of distilled water and a funnel

2. Test Article Description

Horiba Mexa Automotive Emission Analysis System.

3. References

- 3.1 "Code of Federal Regulations," Title 40, Part 86, Subpart B, Sections 89.116, 86.119, and 86.123
- 3.2 Horiba "Automotive Emission Analysis System, Mexa-7000 User's Guide"
- 3.3 Environmental Protection Agency (EPA) current safety policies
- 3.4 "Horiba MEXA 7000 Series Training Manual"

4. Required Equipment

4.1 Horiba Mexa 7000 Automotive Emission Analysis System:

Equipment used: Main Control Unit (MCU)

Interface Control Unit (IFC)

Analyzer Rack (ANR)

Solenoid Valve Unit (SVS)

Sample handling System (SHS)

Power Supply Unit (PSU)

Heated Analyzer (OVN)

Gas Divider (GDC)

Printer

- 4.2 Numbered flexible quick-disconnect jumper lines.
- 4.3 Portable CO₂ interference kit bottle

5. Precautions

5.1 Cylinders containing compressed gases are used for this procedure. The technician must be familiar with the "EPA Laboratory Safety Manual" sections dealing with the safe handling, storage, and use of compressed gas cylinders.

Safety precautions must be followed when using compressed gases.

- 5.2 The Mexa 7000 Automotive Emission Analysis System must warm-up in the standby mode for a minimum of 2 hours after being fully powered up.
- 5.3 Exercise caution when operating heated units. Surface temperature may exceed 60 °C.

6. Visual Inspection

- 6.1 The test cell air handler should be on and test cell ambient conditions are stable.
- 6.2 The gas cylinder and equipment is checked for leakage, damage, and cleanliness.

- 6.7 The power is turned on for the analysis system and related equipment.
- 6.8 The Flame Ionization Detector (FID) is lit.
- 6.9 All documentation needed to operate the analysis system is present.

7. Test Article Preparation

- 7.1 Open the cylinder valve on the C02 bottle and ensure it is set at 14 pounds per square inch (psi).
- 7.2 At the rear of the Solenoid Valve Unit (SVS) verify that the water bubbler reservoir water level is between the blue lines.

If necessary, remove the reservoir cap and add water. See Figure 1.



Figure 1 Water Bubbler

7.3 Connect the flexible quick-disconnect jumper lines between the portable CO2 interference kit bottle and the Solenoid Valve Unit (SVS) disconnect labeled "Bottle."

Note the value of the bottle concentration on the cylinder tag.

7.4 Activate the Horiba Series 7000 Bench.

Additional information is available in the Horiba "Series 7000 Users Guide."

7.5 From the Main Control Unit (MCU) "Command Screen," click on the Horiba logo button in the title bar.

From menu items that appear below the button, click on "User Level."

If "Supervisor" is not the top menu item in the display window, click on "Supervisor."

Use the mouse and on-screen keyboard, see Figure 2, to enter the password. "Supervisor" will appear at the top-center of the screen in the blue area.



Figure 2 On-Screen Keyboard

8. Test Procedure

On the display setup portion of the screen, click on the "Menu" button. See arrow in Figure 3. From the menu items that appear, click on "Utility" (see circle in Figure 3) and the "Utility" screen will appear.




Figure 3 "Utility" screen

102 Click on the "Checks/Tests" button in the command area of the screen. See arrow in Figure 4. From the menu items that appear above the button, click on "Interference Check." See the circle in Figure 4.




Figure 4
Check/Test Button

The "Interference Check" sub-panel will appear. If the bench to be used for testing is not selected on the sub-panel, click on the "Line" button. See arrow in Figure 5. From the menu items that appear, click on the appropriate analyzer bench. See circle in Figure 5.




Figure 5
Interference Screen

104 Click on "C02 Configuration" button. See Figure 7.




Figure 6 C02 Configuration Button

The "C02 Interference Check Config" screen will appear. See Figure 7. Verify the following:

Limits for Line:	Appropriate Bench Number
Min% full scale	0.00
Max% full scale	1.0
FS/PPM Cutoff	300
Min PPM	-3
Max PPM	1

If an item needs correction, click in the field and use the on-screen keypad to enter the correct value. When done, click on "OK" on the keypad.

Click on "OK" from the "C02 Interference Check Config" screen.




Figure 7 C02 Interference Check Config Screen

When "Interference Check" screen appears, click on the "Reset Correction Factor" button. See Figure 8.



Figure 8
Reset Correction Factor screen

The "Interference Check Result Reset" subpanel will appear, click on the "Component" button. See the arrow in Figure 9.

From menu items that appear below the button, click on "CO(L)." See the circle in Figure 9.




Figure 9
Interference Check Results Reset Screen

108 Click on the "Z/S Calibration" button. See the arrow in Figure 10. From menu items that appear below the button, click on "Active." See the circle in Figure 10.




Figure 10 Z/S Calibration Screen

Verify that the field to the right of the "Range" button contains the appropriate range. If not, click on the "Range" button (see the arrow in Figure 11) and from menu items that appear below the button, click on the appropriate range. See the circle in Figure 11.




Figure 11 Select Range Screen

Verify that the field to the right of the "Gas Supply" button contains "External." If not, click on the "Gas Supply" button (see Figure 12) and from menu items that appear below the button, click on "External." See the circle in Figure 12.




Figure 12 Select External Gas Screen

111 Click in the yellow user changeable field for "CO2." Use the on-screen keypad to enter "CE" and to enter the value noted in Step 102. See Figure 13. On the keypad, click on "OK."




Figure 13
Enter C02 Concentration Screen

Verify that the field under "T1" contains "80." See the circle in Figure 14. If not, click in the yellow user changeable field under "T1" and use the on-screen keypad, See Figure X, to enter "80." Click on "OK."




Figure 14 Enter T1 Screen

113 Click on the "Start/Stop" button See Figure 15.




Figure 15 Start/Stop Screen

The "Analyzer Calibration" screen will appear, See Figure 16. When completed, "Calibration successfully completed" will appear. Click on "OK." The "Interference Check Result Reset" panel will appear. If "Calibration Failed" appears, the process was not successful.



Figure 16
Analyzer Calibration Screen

During the test the status will be sequentially displayed in the "Status/Concentration" window. See Figure 17. These status types are "Flowing Zero Gas", "Reading Zero", "Flowing Interference Gas", "Measuring", "Purging with Zero Gas", and "End."




Figure 17
Status Indicators

The value that automatically appears in the "This check" field under "Results" must be within -3.0 to 1.0 PPM, see The circle in Figure 18. If the value is not within acceptable limits, return to Step 113 and repeat the procedure for no more than 3 times. If after 3 attemps the value is not within the acceptable limits, notify a senior technician and wait for instructions before proceeding.

Click on "Update", see the arrow in Figure 18.




Figure 18 Results

117 Click on "Result Display", see Figure 19.




Figure 19 Result Display Button

The "Interference Check Results" subpanel will appear. See Figure 20.




Figure 20 Interference Check Results subpanel

119 Click on the Horiba logo button in the title bar. See the arrow in Figure 21. From the menu items that appear below the button, click on "Hardcopy." See the circle in Figure 21.



Figure 21 Hardcopy subpanel

From menu items that appears, click on "Sub-panel", see Figure 22.




Figure 22 Print Subpanel

- Click anywhere inside the "Interference Check Results" subpanel. The "Interference Check" subpanel will automatically display and a hardcopy of the test results will print on the control room printer. Click on "Cancel." File the print-out in the diagnostics file for the test site.
- The "Utility" screen will appear. Click on the "CO(L)" button. See the arrow in Figure 23. From menu items that appear below the button, click on "Cal." See the circle in Figure 23.



Figure 23 "Utility" Screen

An automatic zero and span calibration check of the analyzer will occur. The indicator flashes "Z" during zero and "S" during span. See Figure 24.

If the "Concentration" window displays "Over" in red letters, repeat this step once. If the "Concentration" window displays "Over" again, notify a senior technician and wait for instructions before proceeding.




Figure 24 Analyzer Calibration Screen

124 Click on the "Horiba" button in the upper left corner of the screen, see Figure the arrow in 25. From the menu items that appear, click on "User Level." See the circle in Figure 25.



Figure 25 Select User Level Screen

From the menu items, click on "Normal." See Figure 26.



Figure 26 Select "Normal" User Screen

9. Data Input

9.1 In the "CO2 Field" of the "Interference Check result reset" screen, the operator enters the value from the gauge of the CO2 Bottle kit.

10. Data Analysis

- 10.1 The operator assures that the C02 bottle is set at 14 pounds per square inch.
- When analyzer calibration is completed, the operator checks the "Interference Check Result Reset" panel to verify that the "Calibration successfully completed" appears.
- 10.3 On the "Interference Check result reset" screen, the value that automatically appears in the "This check" field under "Results" must be within -3.0 to 1.0 PPM.
- 10.4 The operator verifies that the "Concentration" window does not displays "Over" in red letters.

11. Data Output

11.1 A hardcopy of the test results from the The "Interference Check" subpanel are filed in the diagnostics file for the test site.

12. Acceptance Criteria

- 12.1 The C02 bottle must be set at 14 pounds per square inch.
- 12.2 The water bubbler reservoir water level must be between the blue lines.
- 12.3 The "Limits for Line: button:" must be:

Min% full scale 0.00

Max% full scale 1.0

FS/PPM Cutoff 300

Min PPM -3

Max PPM 1

- 12.4 The results of the CO2 Interference test must be within -3.0 to 1.0 PPM. If not within acceptable limits, the test is not repeated more than 3 times.
- 12.5 The "Concentration" window must not display the word "Over."

13. Quality Provisions

- 13.1 The technician ensures all acceptance criteria (Section 12) have been met.
- 13.2 The Mexa 7000 Automotive Emission Analysis System will be warmed-up in the stand-by mode for a minimum of 2 hours.